



DAYTON CITY COUNCIL
REGULAR MEETING
111 S. 1ST Street, Dayton, WA 99328

PRELIMINARY AGENDA

October 23, 2017

9:00 a.m.

1. CALL TO ORDER

A. Roll Call

2. SPECIAL GUESTS AND PUBLIC COMMENT

A. Washington State Auditor – 2014-2016 Audit Entrance Conference

3. UNFINISHED BUSINESS

A. ACTION: Authorize Change Order No. 3, S. 1st St. Reconstruction/Oak St/ S. 2nd St. Water Main Line Replacement, to replace a non-serviceable sewer line in alley located between E. Spring St. and E. Tremont St. from S. 1st Street to S. 2nd Street, increasing the contract by \$21,660.

4. ADJOURN

Next Regular Meeting: **November 8, 2017** at **7:00 p.m.** at Dayton City Hall, 111 S. 1st Street, Dayton, WA 99328.

CHANGE ORDER

Order No.: 3

Date: October 16, 2017

Project/Contract: **South 1st Street Reconstruction (Main Street to Oak Street) and Oak Street/
South 2nd Street Water Main Replacement**

Owner: **City of Dayton, WA**

To: **P.O.W. Contracting, Inc.**

You are hereby requested to comply with the following changes from the contract Documents:

| Description of Changes (Supplemental Description, Plans and Specifications Attached, as applicable) | DECREASE In Contract Price | INCREASE In Contract Price |
|--|-------------------------------|-------------------------------|
| 3-1 Install ±270 linear feet (LF) of 8-inch PVC sewer main, ±8 service connections, one 8-inch cleanout, and gravel surface restoration. | | \$20,000.00 |
| Subtotal | \$0.00 | \$20,000.00 |
| Sales Tax (8.3%) | \$0.00 | \$1,660.00 |
| TOTAL | \$0.00 | \$21,660.00 |
| Net Change in Contract Price | \$0.00 | \$21,660.00 |

JUSTIFICATION:

The existing Orangeburg sanitary sewer main in the alley between Spring Street and Tremont Street, from 1st Street to 2nd Street, has failed in numerous locations and deteriorated to a non-serviceable condition. The existing main will be replaced with 8-inch PVC sewer main from the back sidewalk on South 1st Street, approximately 270 LF, to the northeast end of the existing line. The new sewer main will connect to the 8-inch PVC sewer main in the alley (replaced per Change Order No. 2) near the back of the South 1st Street sidewalk. The grade of the new sewer main will follow approximately that of the existing main, but ±0.5 feet lower in elevation than the existing main. Generally, the work includes potholing to establish grade on the sanitary sewer main, connecting to the 8-inch PVC sewer main near South 1st Street, installing ±270 LF of 8-inch PVC sewer main including pipe bedding, wyes and connections to approximately eight sewer services (connections will be made at the edge of the trench and will not extend to the property line), 8-inch cleanout with cast iron cover at the northeast end of the sewer main, backfill and compact trench with native material, 1-foot thick gravel surface restoration (CSTC or CSBC) within the disturbed area, and excavation and haul of material removed from trench.

The amount of the Contract will be increased by the sum of: \$21,660.00

Twenty-one thousand six hundred sixty and 00/100 ----- Dollars

The Contract total including this and previous Change Orders will be: \$1,262,210.32

One million two hundred sixty-two thousand two hundred ten and 32/100 ----- Dollars

The Contract period provided for completion will be increased: 4 working days

Revised Date of Substantial Completion: October 13, 2017

This document will become a supplement to the Contract and all provisions will apply hereto.

| | | |
|-------------|--|----------------------|
| Approved | P.O.W. Contracting, Inc. | (Date) |
| Recommended |  Anderson Perry & Associates, Inc. | 10/17/2017 (Date) |
| Approved | City of Dayton, WA | (Date) |